

Table 8.16.: Acceptance Tests for Fire Detection and Alarm System	
ITEM	REQUIREMENTS
2. ACCEPTANCE	6. OPERATIONAL/ FUNCTIONAL TESTS
TESTS	 i. Notify 24 X 7 and Civil Defence of the Functional tests. ii. Disconnect any suppression systems monitored and triggered by the Fire Detection and Alarm System to be tested. iii. The following operational and functional tests shall be conducted.
	7. SECONDARY POWER
	i. Load voltage verification.ii. Discharge test.iii. Charger tests.
	<u>8. FACP</u>
	 i. Functional tests of FACP Lamps, LEDS and LCD. ii. Fuses: Removal and normalization. iii. Disconnect switches operation. iv. Trouble signals initiation (open wire, loop, unlock detectors etc.) v. Trouble signal normalization. vi. Ground fault monitoring. vii. Annunciation to remote panels.
	9. INITIATING DEVICES
	 Trigger alarm through smoke detectors using listed aerosol . Trigger alarm through operating manual call points. Trigger alarm through heat detectors by heat blower. Verify alarm signal generation. Verify annunciator alarms and displays. Verify the location displays and confirm addresses of initiating device. Verify following interconnected systems upon alarm signal.
	10. INTERCONNECTED SYSTEMS
	 i. Interconnected systems such as HVAC shut down, dampers, doors, elevators are functioning satisfactorily. ii. The interconnected systems are monitored and supervised. iii. Disconnect, initiate trouble signal and normalize.
	11. NOTIFICATION DEVICES
	 i. Audibility is clear. And within the acceptable strength. ii. Voice messages are clear and comprehendible. iii. Visual notifications are satisfactory and convey the alarm. iv. Verify supervision of notification devices. Initiate trouble and restore.